

# **MUNICIPAL CORPORATION KOTA**

## **‘G’ SCHEDULE (NIT NO. 13/2017-18) (Copy No. 03)**

Name of Work : वार्ड नं. 29, गोविन्द नगर मे स्थित नाला निर्माण एवं मरम्मत कार्य ।

Estimated Cost : **Rs. 14.75 Lacs** Earnest Money: **7375/- (0.50%)**

Processing Fee : **500/-** **29500/- (2%)**

Tender Cost : **1500/-** Completion Period : **2 Month**

Date of Downloading of Tender (Website) : **05.05.2017 To 28.05.2017**

Date of online submission of Tender : **05.05.2017 To 28.05.2017**

Date of Opening Tender/ Technical Bid : **30.05.2017 (3:00 PM) (Envelop – A)**

Date of Opening Financial Bid : **After testing the technical bid**

Issued To: \_\_\_\_\_

C.R.No. \_\_\_\_\_ Dated \_\_\_\_\_

S.NO	Particulars	Qty.	Rate	Amount
1	Silt clearance of drains, channels and canals with lift 1.5 mtr. and lead upto 50 mtr.	300.00 Cum	48.00 P. Cum	14400.00
2	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 mtr. lead.	300.0 Sqm	43.00 P.sqm	12900.0
3	Demolishing cement concrete including disposal of material within 50 meters lead : 1 : 3 : 6 richer mix.	10.0 Cum	388.00 P.cum	3880.00
4	Dismantling stone rubble masonry including stacking of serviceable material and disposal of unserviceable material within 50 meters lead. In cement mortar.	15.0 cum	392.00 P. Cum	5880.00

5	Dismantling stone slab roofing over wooden karries and battens (dismantling karries and battens to be paid for separately) including stacking of serviceable material and disposal of unserviceable material with in 50 meters lead.	5.00 Cum	426.00 P. cum	2130.00
6	Demolishing of R.C.C. work including stacking of steel bar and disposal of steal bar and disposal of unsuitable material within 50mm lead.	6.00 Cum	567.00 P.cum	3402.00
7	Earthwork in excavation in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5mtr. including taking out the excavated soil and depositing and refilling of jhiri with watering and ramming and disposal of surplus excavated soil as directed within a lead of 50 mtr. All kinds of soil.	20.00 Cum	152.00 P. Cum	3040.00
8	Pumping out water caused by springs, tidal or river seepage, broken water mains or drains and the like with pumping set of following H.P. including P.O.L. / Power consumption etc. complete. 5 to 9 H.P.  L.S. 200 Hours	200.0 Hour	130.00 Per Hour	26000.00
9	Transportation of excavation material from site including loading and loading and unloading etc complete with in lead 10 k.m. Earth, sand, lime, morrum, maure or sludge. L.S. 350 Cum	300.00 Cum	81.00 P. cum	24300.00
10	Providing and laying in position cement concrete including curing, compaction etc. complete in specified grade excluding the cost the cost of centering and shuttering – All work upto plinth level.			

	(A) 1:4:8 (1 cement : 5 coarse sand : 8 graded stone aggregate 40 mm nominal size	35.0 Cum	2497.0 P.cum	87395.0
	(B) 1:1.5:3 (1 cement :1.5 coarse sand : 3 graded stone aggregate 20mm nominal size).	60.00	3711.0 P.Cum	222660.00
11	R/R Stone masonry for foundation and Plinth in cement sand mortar for wall in cement sand mortar 1 : 6 (1 cement :6 sand) above 30 cm thick walls.	16.0 Cum	2014.0 P.Cum	32224.00
12	Providing and laying damp-proof course with cement concrete grade M-150 (1 : 2 : 4) mortar prepared with 1% solution of water – proof compound) excluding two coats of hot blown bitumen (2 kg. per sqm) complete as per specification without glass strip 3mm thick at a distance of 1 m. interval. 50 mm thick.	180.00 Sqm	115.00 Per Sqm	20700.00
13	Plaster on new surface of walls in cement sand mortar 1 : 4 including racking of Joints etc. complete finished. 20mm thick.	80.0 Sqm	120.0 P.Sqm	9600.00
14	Centering and shuttering with plywood or steel sheets including strutting , propping, bracing both ways and removal of formwork for foundations in basements rafts, footings, strap beams, bases of columns etc. upto plinth level.	450.0 Sqm	91.00 P.sqm	40950.00

15	<p>Providing and fabricating reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding (including cost of binding wire) all complete up to floor three level.</p> <p>Cold twisted deformed bars (IS:1786)</p> <p>l.s. 3750.0kg</p>	<p>3750.0</p> <p>kg</p>	<p>66.0</p> <p>P.Kg.</p>	<p>247500.00</p>
16	<p>Providing and laying in position specified grade of reinforced cement concrete including curing compaction finishing with rendering in cement sand mortar 1 : 3 (1 cement : 3 coarse sand) and making good the joints excluding the cost of centering, shuttering and reinforcement all work up to plinth level 1 : 1.5 : 3 (1cement : 1.5 coarse sand : 3 graded store aggregate 20 mm nominal size.</p>	<p>90.00</p> <p>Cum</p>	<p>4027.00</p> <p>P.cum</p>	<p>362430.00</p>
17	<p>Providing and fixing steel gate grating and grills made of angles, tees, square bars or other flats black pipe with holdfast and fittings complete as per design and drawing including cutting welding and fabrication with priming coat of red oxide.</p> <p>L.S. 500.00</p>	<p>500.0</p> <p>K.g.</p>	<p>78.00</p> <p>P.K.g.</p>	<p>39000.00</p>

18	35mm thick Rough Chisel dressed stone flooring of approved shade set in pattern over 20mm thick base of cement mortar 1:6 and Joint finished with cement sand mortar 1 : 3 complete in all respects Red sand stone.	75.00 Sqm	360.0 P.Sqm	27000.00
19	Supplying and fixing of stone linted / bed plats of approved quarry rough dressed in cement mortar 1 : 4. upto 15 cm thick.	24.00 Cum	11490.00 P.cum	275760.00
20	Flyash Brick masonry in foundation and plinth with Flyash bricks of class designation 75 in : Cement mortar 1:6 (1 cement : 6 coarse sand).	5.00 Cum	2696.00 P.cum	13480.00
<b>Total</b>				<b>1474631.00</b>

**Terms & Conditions:**

1. Conditional tender shall not be accepted.
2. In case of any error in rates or nomenclature, the same shall be paid as per B.S.R. of P.W.D. 2013.
3. निविदा दर बी.एस.आर. से कम होने पर अन्तर राशि की बैंक गारन्टी / डी. डी. विभाग में टेण्डर स्वीकृत होने के 15 दिवस के अन्दर-अन्दर जमा कराना होगा, अन्यथा धरोहर राशि जब्त की जाकर निविदा निरस्त कर दी जावेगी।

***I / We hereby agree to execute the work :***

@ \_\_\_\_\_ % above/below (in words)

@ \_\_\_\_\_ % above/below (in Figures)

***Signature of Contractor***

***Executive Engineer  
Municipal Corporation, Kota***

—प्रारूप—

(लेटरहेड)

सहमति—पत्र

श्रीमान अधिशाषी अभियन्ता,  
नगर निगम कोटा।

**विषय : अपनी निविदा हेतु सहमति के संबंध में।**

महोदय,

विषयान्तर्गत निवेदन है कि मैं सत्यनिष्ठा पूर्वक अपनी निम्न सहमति प्रस्तुत करता हूँ :-

- 1) निविदा प्रपत्र पर मेरे स्वयं के हस्ताक्षर है।
- 2) निविदा दर स्वयं मेरे द्वारा भरी गई है।
- 3) मेरे द्वारा प्रस्तुत रजिस्ट्रेशन मेरा स्वयं का है एवम् पूर्णतया वैध है।
- 4) कार्य मेरे द्वारा ही सम्पादित किया जायेगा एवं इसे Sublet नहीं किया जायेगा।
- 5) किसी भी प्रकार की गलत जानकारी के लिये मैं स्वयं उत्तरदायी रहूँगा।

दिनांक : .....

(हस्ताक्षर संवेदक मय सील)