

MUNICIPAL CORPORATION KOTA

'G' SCHEDULE (NIT NO. 13/2017-18) (Copy No. 06)

Name of Work : वार्ड नं. 33, अमर विहार केनाल रोड मे सी.सी. रोड निर्माण कार्य।
(विधायक कोष)

Estimated Cost : **Rs. 5.00 Lacs** Earnest Money: **2500/- (0.50%)**

Processing Fee : **500/-** **1000/- (2%)**

Tender Cost : **500/-** Completion Period : **3 Month**

Date of Downloading of Tender (Website) : **05.05.2017 To 28.05.2017**

Date of online submission of Tender : **05.05.2017 To 28.05.2017**

Date of Opening Tender/ Technical Bid : **30.05.2017 (3:00 PM) (Envelop – A)**

Date of Opening Financial Bid : **After testing the technical bid**

Issued To: _____

C.R.No. _____ Dated _____

S.NO	Particulars	Qty.	Rate	Amount
1	Earthwork in excavation in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5mtr. including taking out the excavated soil and depositing and refilling of jhiri with watering and ramming and disposal of surplus excavated soil as directed within a lead of 50 mtr. All kinds of soil.	42.00	152.00 P. Cum	6384.00
2	Construction of granular sub-base by providing well graded material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. For Grading III Material	31.86	373.00 P. Cum	11883.78
3	Providing and laying in position cement concrete including curing compaction etc. complete in specified grade excluding the cost of centering and shuttering – All work upto plinth level. 1 : 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	42.00	2497.00 P.cum	104874.00

4	Providing and laying in position including curing, compaction etc. complete in specified grade excluding the cost of centering and shuttering – All work up to plinth level. 1 : 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	63.00	3711.00 P.cum	233793.00
5	Rough chisel dressed stone flooring over 20mm (AV.) thick base in CM 1 : 6 including pointing with cement mortar 1 : 2 (1 cement : 2 stone dust) with and admixture of pigment to match the shade of stone with joint thickness upto 15 mm : 35 mm thick red sand stone.	157.50	360.00 P.sqm	56700.00
6	Random Rubble stone masonry for foundation and plinth in cement Sand mortar above 30 cm thick wall in : Cement Mortar 1 : 6 (1- Cement : 6 Sand)	33.07	2014.00 P.cum	66613.05
7	Providing and laying damp-proof course 75 mm thick with cement sand mortar 1 : 3 including two coats of hot blown bitumen (2 Kg. per Sqm) complete as per specification. 50 mm thick.	73.50	115.00 P.sqm	8452.50
8	Plaster on new surface on walls in cement sand mortar 1 : 4 including racking of joints etc. complete fine finish. 20 mm thick	94.50	120.00 P.cum	11340.00
Total				500039.83

Say Amount Rs. – 5.00 Lacs

Terms & Conditions:

1. Conditional tender shall not be accepted.
2. In case of any error in rates or nomenclature, the same shall be paid as per B.S.R. of P.W.D. 2013.
3. निविदा दर बी.एस.आर. से कम होने पर अन्तर राशि की बैंक गारन्टी / डी. डी. विभाग में टेण्डर स्वीकृत होने के 15 दिवस के अन्दर-अन्दर जमा कराना होगा, अन्यथा धरोहर राशि जब्त की जाकर निविदा निरस्त कर दी जावेगी।

I / We hereby agree to execute the work :

@ _____ % above/below (in words)

@ _____ % above/below (in Figures)

Signature of Contractor

**Executive Engineer
Municipal Corporation, Kota**

—प्रारूप—

(लेटरहेड)

सहमति—पत्र

श्रीमान अधिशाषी अभियन्ता,
नगर निगम कोटा।

विषय : अपनी निविदा हेतु सहमति के संबंध में।

महोदय,

विषयान्तर्गत निवेदन है कि मैं सत्यनिष्ठा पूर्वक अपनी निम्न सहमति प्रस्तुत करता हूँ :-

- 1) निविदा प्रपत्र पर मेरे स्वयं के हस्ताक्षर हैं।
- 2) निविदा दर स्वयं मेरे द्वारा भरी गई है।
- 3) मेरे द्वारा प्रस्तुत रजिस्ट्रेशन मेरा स्वयं का है एवम् पूर्णतया वैध है।
- 4) कार्य मेरे द्वारा ही सम्पादित किया जायेगा एवं इसे Sublet नहीं किया जायेगा।
- 5) किसी भी प्रकार की गलत जानकारी के लिये मैं स्वयं उत्तरदायी रहूँगा।

दिनांक :

(हस्ताक्षर संवेदक मय सील)