

MUNICIPAL CORPORATION KOTA

‘G’ SCHEDULE (NIT NO. 13/2017-18) (Copy No. 09)

Name of Work : नगर निगम निर्माण खण्ड तृतीय मे लखावा क्षेत्र मे तलाब मे वर्षाकाल पूर्व एवं वर्षाकाल के दौरान लखावा तालाब की सुरक्षा हेतु मिटटी के कटटे एवं क्वारी रबिश डालने का कार्य।

Estimated Cost : **Rs. 7.00 Lacs** Earnest Money: **3500/- (0.50%)**
 Processing Fee : **500/-** **14000/- (2%)**
 Tender Cost : **1000/-** Completion Period : **4 Month**
 Date of Downloading of Tender (Website) : **05.05.2017 To 28.05.2017**
 Date of online submission of Tender : **05.05.2017 To 28.05.2017**
 Date of Opening Tender/ Technical Bid : **30.05.2017 (3:00 PM) (Envelop – A)**
 Date of Opening Financial Bid : **After testing the technical bid**

Issued To: _____

C.R.No. _____ Dated _____

Part – A (Civil Work)

PWD BSR 2013

S.N.	Particulars	Qty.	Rate (Rs.)	Amount (Rs.)
1	Clearing and grubbing road land including wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300 mm, removal of stumps of such trees cut earlier and disposal of unserviceable, upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150 mm in thickness as per technical specification clause 201. In area of thorny jungle.	0.80	39025.00 P. Hectare	31220.00
2	Earth Work in excavation in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 Mtr including taking out the excavated soil and depositing and refilling of jhiri with watering and ramming and ramming and disposal of surplus excavated soil as directed within a lead of 50m. All Kinds of Soil.	50.00	152.0 P.Cum	7600.00
3	R/R Stone masonry for foundation and Plinth in cement sand mortar for wall in cement sand mortar 1 : 3 (1 cement : 3 sand) above 30 cm thick walls.	2.00	2391.00 P.Cum	4782.00
4	Plaster on new surface of walls in cement sand mortar 1: 3 including racking of Joints etc. complete finished 25mm thick.	10.00	168.0 P.Sqm	1680.00

5	R/R Stone masonry for foundation and Plinth in cement sand mortar above 30 cm thick walls in. Dry stone.	5.00	1132.0 P.Cum	5660.00
6	Supply of Crusher Stone chipping / Screening at Quarry. 4.75 mm nominal size.	25.00	650.00 P.Cum	16250.00
7	Spreading or manure and good earth in required thickness (cost of manure and good earth to be paid separately). (Crusher Stone chipping) 4.75 mm nominal size.	25.00	5.00 P.cum	125.00
8	Granular Sub-base with Well Graded Material (Table 400.1) By Mix in Place Method : Construction of granular sub-base by providing well graded material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. For Grading III Material	200.00	402.00 P.Cum	80400.00
9	Random rubble dry stone Kharanja under floor.	20.00	805.00 Per Cum	40250.00
Total Part - A				187967.00

Part – B (H – Schedule)

Non BSR Item

S.No.	Particulars	Qty.	Rate	Amount (Rs.)
1	Supply & filling and stitching of empty bags of capacity 50 Kg. Per bag with earth available at site weight not less than 40 Kg. including excavation etc. complete. As plastic bags. Lakahawa Talab.	6000.00 Nos.	9.50 Each	57000.00
2	Labour Charges for making coffer damping bund by loading transporting of earth filled cement bags dropping at required locations in water including all leads and lift complete excluding the cost of cement bags. Lakahawa Talab.	6000.00 Nos.	14.25 Each	85500.00

3	Hire Charges for tractor with trolley (with lifting arrangements) above 26 Hp to 40 HP including POL & Driver (1 Day = 8 working hrs.) at Lakahawa Tank Site. I. 4 Nos. Tractor & trolley x 20 days = 80Days II. 1 No. Tractor with water tanker 1 x 20 days = 20 Days 100 Days	36.00 Day	2450.00 Per Day (or 8 hrs.)	88200.00
4	Hire Charges for JCB excavator cum loader including POL and operational staff all respect at Lakahawa Tank Site. 1 Nos. JCB x 20 days	20.00 Day	8000.00 Per Day (or 8 hrs.)	160000.00
Total Part - B				390700.00

Part – C (Watch & ward)

S.N.	Particulars	Qty.	Rate (Rs.)	Amount (Rs.)
1	Engaged civil mistry, road inspector, road mistry, stone dresser (Silawat), Tailor as a gauge reader for rainy season i.e. Form 15 Jun 2015 to 15 September 2015 (3 Months) . 3 month x 3 shifts x 30 days = 270 Days	270.00 Days	250.00 P. Day	67500.00
2	Supply of labour of lakhawa Tank Site in 3 Shifts . Lakahawa talab. 4 Nos. x 3 Mount x 30 days	360.00 Nos.	150.00 Each	54000.00
Total Part - C				121500.00

Grand Total Part (A+B+C) = 187967 + 390700 + 121500 = 700167.00

Say Amount Rs. = 7.00 Lacs

Terms & Conditions:

1. Conditional tender shall not be accepted.
2. In case of any error in rates or nomenclature, the same shall be paid as per B.S.R. of P.W.D. 2013.
3. निविदा दर बी.एस.आर. से कम होने पर अन्तर राशि की बैंक गारन्टी / डी. डी. विभाग में टेण्डर स्वीकृत होने के 15 दिवस के अन्दर-अन्दर जमा कराना होगा, अन्यथा धरोहर राशि जब्त की जाकर निविदा निरस्त कर दी जावेगी।

I / We hereby agree to execute the work :

@_____ % above/below (in words)

@_____ % above/below (in Figures)

Signature of Contractor

***Executive Engineer
Municipal Corporation, Kota***

—प्रारूप—

(लेटरहेड)

सहमति—पत्र

श्रीमान अधिशाषी अभियन्ता,
नगर निगम कोटा।

विषय : अपनी निविदा हेतु सहमति के संबंध में।

महोदय,

विषयान्तर्गत निवेदन है कि मैं सत्यनिष्ठा पूर्वक अपनी निम्न सहमति प्रस्तुत करता हूँ :-

- 1) निविदा प्रपत्र पर मेरे स्वयं के हस्ताक्षर हैं।
- 2) निविदा दर स्वयं मेरे द्वारा भरी गई है।
- 3) मेरे द्वारा प्रस्तुत रजिस्ट्रेशन मेरा स्वयं का है एवम् पूर्णतया वैध है।
- 4) कार्य मेरे द्वारा ही सम्पादित किया जायेगा एवं इसे Sublet नहीं किया जायेगा।
- 5) किसी भी प्रकार की गलत जानकारी के लिये मैं स्वयं उत्तरदायी रहूँगा।

दिनांक :

(हस्ताक्षर संवेदक मय सील)