

MUNICIPAL CORPORATION KOTA

(NIT NO. 17/2017-18) ('G' Schedule) (Copy No. 03)

Name of Work : वार्ड नं. 40 में विभिन्न स्थानों पर नाली पटान सी सी लोहे के चेम्बर इन्टरलॉकिंग टीन शेड निर्माण कार्य।

Estimated Cost : **Rs. 10.64 Lacs** Earnest Money : **5320/- (0.50%)**
21280/- (2%)

Tender Cost : **1500/-** Completion Period : **2 Month**

Processing Fees : **500/-**

Date of Sale of Tender : **16-05-2017 to 07-06-2017**

Date of Receipt Tender : **16-05-2017 to 07-06-2017 (Office Time)**

Date of Opening Tender : **08-06-2017 (2.00 PM) (Envelop – A)**

Date of Opening Tender : **तकनीकी बिड परीक्षण के पश्चात्।**

Issued To: _____

C.R.No. _____ Dated _____

PART – A

S.NO	Particulars	Qty.	Rate	Amount
1	Silt clearance of drains, channel and canals with lift 1.5 Mtr. and lead up to 50 Mtr.	50.00 Cum	48.00 P.cum	2400.00
2	Earth Work in excavation in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 mtr. including taking out the excavated soil and depositing and refilling of jhiri with watering and ramming and disposal of surplus excavated soil as directed within a lead of 50mtr. All kinds of soil	150.00 Cum	152.00 P.cum	22800.00
3	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 mtr. lead.	150.00 Sqm	43.00 P.sqm	6450.00
4	Demolishing cement concrete including disposal of material within 50 meters lead : 1 : 3 : 6 richer mix.	15.00 Cum	388.00 P.cum	5820.00
5	Dismantling stone slab roofing over wooden karries and battens (dismantling karries and battens to be paid for separately) including stacking of serviceable material and disposal of unserviceable material with in 50 meters lead.	1.50 Cum	426.00 P.cum	639.00
6	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground with in 50 meter lead .	150.00 Sqm	6.50 P.sqm	975.00
7	Transportation of excavation of earth from site with loading and unloading etc. complete with all lead and lift. Lead 1 km	200.00 Cum	90.90 P.cum	18180.00
8	providing and laying in position including curing, compaction etc. complete in specified grade excluding the cost of	15.00 Cum	2284.00 Cum	34260.00

	centering and shuttering – All work up to plinth level. cement concrete (1 : 5 : 10)			
	1 : 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	100.00 Cum	3711.00 P.cum	371100.00
	1 : 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	60.00 Cum	2497.00 P.cum	149820.00
9	Random Rubble stone masonry for foundation and plinth in cement Sand mortar above 30 cm thick wall in : Cement Mortar 1 : 6 (1- Cement : 6 Sand)	38.00 Cum	2014.00 P.cum	76532.00
10	Flyash Brick masonry in foundation and plinth with bricks of class designation 75 in : Cement mortar 1:6 (1 cement : 6	5.02 Cum	2696.00 P.cum	13533.92
11	Supplying and fixing of stone linted / bed plats of approved quarry rough dressed in cement mortar 1 : 4. upto 15 cm thick.	0.75 Cum	11490.00 P.cum	8617.50
12	Plaster on new surface on walls in cement sand mortar 1 : 4 including racking of joints etc. complete fine finish. 20 mm thick	200.00 Sqm	120.00 P.sqm	24000.00
13	Providing and laying damp proof with cement concrete grade M-15 (1:2:4) mortar prepared with 15 solution of water proof compound including including two coats of hot blown bitumen (2 kg. per sqm0 complete as per specification with glass strip 3 mm thick at a distance of 1 m interval. 50 mm thick	90.00 Sqm	115.00 P.sqm	10350.00
14	Providing and laying of interlocking Concrete Block Pavements having thickness 80 mm as per drawing and technical specification clause 1504	80.00 Sqm	643.04 P.sqm	51443.20
15	Rough chisel dressed stone flooring over 20mm (AV.) thick base in CM 1 : 6 including pointing with cement mortar 1 : 2 (1 cement : 2 stone dust) with and admixture of pigment to match the shade of stone with joint thickness upto 15 mm : 35 mm thick red sand stone. New work	300.00 Sqm	360.00 P.sqm	108000.00
16	Structural steel work welded in built up sections, trusses and framed work including cutting, hosting fixing in position and applying a priming coat of approved steel primer all complete above plinth level upto 4.5 mtr height in R.S. joist flats, tees, angles and channels.	500.00 Kg.	68.00 P.Kg,	34000.00
17	Providing and fixing Ist quality white / Ivory Glazed Tiles ISI marked (1S : 13753) of size 300mm x 200mm in walls, floors, steps, pillars, etc. laid on a bed of neat cement slurry finished with flush pointing in white cement mixed with pigment to match the shade of tile	20.00 Sqm	563.00 P.sqm	11260.00

	complete (excluding the cost of cement plaster) Category - II Bell, Thar make etc.			
18	Providing Corrugated G.I. Sheet roofing fixed with G.I.J. or L-hooks bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved paint of over lapping of sheet complete (upto a pitch of 60 ⁰) and excluding the cost of purloins, rafters and trusses, for class of sheets : 1 mm thick.	35.00 Sqm	768.00 P.sqm	26880.00
19	Providing and fixing steel gate grating and grills made of angles, tees, square bars or other flats black pipe with holdfast and fittings complete as per design and drawing including cutting welding and fabrication with priming coat or red oxide.	500.00 kg.	78.00 P.Kg.	39000.00
20	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade including all scaffolding : (a) New work (two or more coats) over and including scrapping and priming coat with cement primer. (b) Old work (one or more coats) including scrapping surface and necessary repairs	30.00 Sqm 20.00 Sqm	52.00 P.sqm 17.00 P.sqm	1560.00 340.00
21	Painting with enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work one or more coats on old work	30.00 Sqm 20.00 Sqm	46.00 P.sqm 30.00 P.sqm	1380.00 600.00
22	Polished Blue Kota stone flooring skirting laid over 20mm thick base of CM 1 : 4 and jointed with grey cement slurry to mach the shade of the slab including rubbing and polishing complete. For area of each slab upto 901 to 2000 sq.Cm. 30 mm thick slab. 30 mm thick slab	27.00 Sqm	528.00 P.sqm	14256.00
23	Centering and shuttering with plywood or steel sheets including strutting , propping, bracing both ways and removal of formwork for foundations in baseess)ments rafts, footings, strap beams, bases of columns etc. upto plinth level.	22.00 Sqm	91.00 P.sqm	2002.00
24	Providing and laying in position specified grade of reinforced cement concrete including curing compaction finishing with rendering in cement sand mortar 1 : 3 (1 cement : 3 coarse sand) and making good the joints excluding the cost of centering, shuttering and rein for cement all work up to plinth level 1 : 1.5 : 3	7.00 Cum	4027.00 P.cum	28189.00

	(1cement : 1.5 coarse sand : 3 graded store aggregate 20 mm nominal size			
	TOTAL			1064387.62

Say Rs. 10.64 Lacs

Terms & Conditions:

1. Conditional tender shall not be accepted.
2. In case of any error in rates or nomenclature, the same shall be paid as per B.S.R. of P.W.D. 2013.
3. निविदा दर बी.एस.आर. से कम होने पर अन्तर राशि की बैंक गारन्टी / डी. डी. विभाग में टेण्डर स्वीकृत होने के 15 दिवस के अन्दर-अन्दर जमा कराना होगा, अन्यथा धरोहर राशि जब्त की जाकर निविदा निरस्त कर दी जावेगी।

I / We hereby agree to execute the work :

At the rate _____ % above/below (in words)

At the rate _____ % above/below (in Figures)

Signature of Contractor

**Executive Engineer
Municipal Corporation, Kota**

—प्रारूप—

(लेटरहेड)

सहमति—पत्र

श्रीमान अधिशाषी अभियन्ता,
नगर निगम कोटा।

विषय : अपनी निविदा हेतु सहमति के संबंध में।

प्रसंग : निविदा क्रमांक.....

महोदय,

विषयान्तर्गत निवेदन है कि मैं सत्यनिष्ठा पूर्वक अपनी निम्न सहमति प्रस्तुत करता हूँ :-

- 1) निविदा प्रपत्र पर मेरे स्वयं के हस्ताक्षर हैं।
- 2) निविदा दर स्वयं मेरे द्वारा भरी गई है।
- 3) मेरे द्वारा प्रस्तुत रजिस्ट्रेशन मेरा स्वयं का है एवम् पूर्णतया वैध है।
- 4) कार्य मेरे द्वारा ही सम्पादित किया जायेगा एवं इसे Sublet नहीं किया जायेगा।
- 5) किसी भी प्रकार की गलत जानकारी के लिये मैं स्वयं उत्तरदायी रहूँगा।

दिनांक :

(हस्ताक्षर संवेदक मय सील)