

MUNICIPAL CORPORATION KOTA

(NIT NO. 17/2017-18) ('G' Schedule) (Copy No. 06)

Name of Work : वार्ड नं. 36 में सोफिया स्कूल नाला, शिवाजी कॉलोनी सी सी नाली निर्माण कार्य।

Estimated Cost : **Rs. 30.00 Lacs** Earnest Money : **15000/- (0.50%)**
60000/- (2%)

Tender Cost : **2000/-** Completion Period : **6 Month**

Processing Fees : **500/-**

Date of Sale of Tender : **16-05-2017 to 07-06-2017**

Date of Receipt Tender : **16-05-2017 to 07-06-2017 (Office Time)**

Date of Opening Tender : **08-06-2017 (2.00 PM) (Envelop – A)**

Date of Opening Tender : **तकनीकी बिड परीक्षण के पश्चात्।**

Issued To: _____

C.R.No. _____ Dated _____

PART – A

S.NO	Particulars	Qty.	Rate	Amount
1	Silt clearance of drains, channel and canals with lift 1.5 Mtr. and lead up to 50 Mtr.	207.24 Cum	48.00 P.cum	9947.52
2	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 mtr. lead.	244.80 Sqm	43.00 P.sqm	10526.40
3	Dismantling of flexible pavements and disposal of dismantled materials upto a lead of 100 m stacking serviceable and unserviceable materials separately as per technical specification clause 202 (i) by manual means (a) Bituminous Courses	184.00 Cum	378.00 P.cum	69552.00
4	Transportation of excavation of earth from site with loading and unloading etc. complete with all lead and lift. Lead 1 km	350.00 Cum	90.90 P.cum	31815.00
5	Random Rubble stone masonry for foundation and plinth in cement Sand mortar above 30 cm thick wall in : Cement Mortar 1 : 6 (1- Cement : 6 Sand)	481.04 Cum	2014.00 P.cum	968814.56
6	Providing and laying damp proof with cement concrete grade M-15 (1:2:4) mortar prepared with 15 solution of water proof compound including including two coats of hot blown bitumen (2 kg. per sqm) complete as per specification with glass strip 3 mm thick at a distance of 1 m interval. 50 mm thick	302.80 Sqm	115.00 P.sqm	34822.00
7	Plaster on new surface on walls in cement sand mortar 1 : 4 including racking of joints etc. complete fine finish. 20 mm	780.00 Sqm	120.00 P.sqm	93600.00

	thick			
8	Providing and laying of interlocking Concrete Block Pavements having thickness 80 mm as per drawing and technical specification clause 1504	540.00 Sqm	643.04 P.cum	347241.60
9	Providing and laying in position cement concrete including curing compaction etc. complete in specified grade excluding the cost of centering and shuttering – All work upto plinth level. 1 : 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	160.80 Cum	2497.00 P.cum	401517.60
10	Supplying and fixing of stone linted / bed plats of approved quarry rough dressed in cement mortar 1 : 4 upto 15 cm thick.	2.76 Cum	11490.00 P.cum	31712.40
11	Providing and laying in position cement concrete including curing compaction etc. complete in specified grade excluding the cost of centering and shuttering – All work upto plinth level. 1 : 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	150.00 Cum	3711.00 P.cum	556650.00
12	Earth Work in excavation in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 Mtr including taking out the excavated soil and depositing and refilling of jhiri with watering and ramming and ramming and disposal of surplus excavated soil as directed within a lead of 50m. All Kinds of Soil	189.00 Cum	152.00 P.cum	28728.00
13	Random Rubble dry stone Kharnaja under floor.	96.60 Cum	805.00 P.cum	77763.00
14	Brick masnory in founfdation and plinth with bricks of class designation 75 in cm 1:6	46.00 Cum	2942.00 P.cum	135332.00
15	Providing and fabricating reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding (including cost of binding wire) all complete up to floor three level. Cold twisted deformed bars (IS:1786).	500.00 Kg.	66.00 P.Kg.	33000.00
16	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, post and struts etc. up to floor three level including curing, compaction, finishing with rendering in cement sand mortar 1:3 (1 cement : 3 coarse sand) and making good the joints excluding cost of centering shuttering and 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	6.12 Cum	4149.00 P.cum	25391.88
17	Providing and laying in position specified grade of reinforced cement concrete including curing compaction finishing with rendering in cement sand mortar 1 : 3 (1 cement : 3 coarse sand) and making good the joints excluding the cost of centering, shuttering and rein for cement all work up to plinth level 1 : 1.5 : 3 (1cement : 1.5 coarse sand : 3 graded store aggregate 20 mm nominal size	5.40 Cum	4027.00 P.cum	21745.80

18	Suspended floors, roofs landing staircase, balconies, girders, cantilevers, bands, coping bed plats, anchor blocks, sills, chajjas, lintel, beam etc. columns, pillars, posts and struts etc.	18.00 Sqm	211.00 P.sqm	3798.00
19	Centering and shuttering with plywood or steel sheets including strutting , propping, bracing both ways with wooden members and removal of form work for superstructure upto 4.5m height above plinth level for suspended floors , roofs , landing staircases ,balconies, girders ,cantilevers , bands , copings , bed plates , anchor blocks, sills , chhajjsa, lintel, beam, etc.	9.00 Sqm	153.00 P.sqm	1377.00
20	Rough chisel dressed stone flooring over 20mm (AV.) thick base in CM 1 : 6 including pointing with cement mortar 1 : 2 (1 cement : 2 stone dust) with and admixture of pigment to match the shade of stone with joint thickness upto 15 mm : 35 mm thick red sand stone. New work	316.80 Sqm	360.00 P.sqm	114048.00
21	Providing and fixing reinforcement ferro cement drain cover	9.60 Sqm	50.00 P.sqm	480.00
TOTAL				2997862.76

Say Rs. 30.00 Lacs

Terms & Conditions:

1. Conditional tender shall not be accepted.
2. In case of any error in rates or nomenclature, the same shall be paid as per B.S.R. of P.W.D. 2013.
3. निविदा दर बी.एस.आर. से कम होने पर अन्तर राशि की बैंक गारन्टी / डी. डी. विभाग में टेण्डर स्वीकृत होने के 15 दिवस के अन्दर-अन्दर जमा कराना होगा, अन्यथा धरोहर राशि जब्त की जाकर निविदा निरस्त कर दी जावेगी।

I / We hereby agree to execute the work :

At the rate _____ % above/below (in words)

At the rate _____ % above/below (in Figures)

Signature of Contractor

***Executive Engineer
Municipal Corporation, Kota***

—प्रारूप—

(लेटरहेड)

सहमति—पत्र

श्रीमान अधिशाषी अभियन्ता,

नगर निगम कोटा।

विषय : अपनी निविदा हेतु सहमति के संबंध में।

प्रसंग : निविदा क्रमांक.....

महोदय,

विषयान्तर्गत निवेदन है कि मैं सत्यनिष्ठा पूर्वक अपनी निम्न सहमति प्रस्तुत करता हूँ :-

- 1) निविदा प्रपत्र पर मेरे स्वयं के हस्ताक्षर हैं।
- 2) निविदा दर स्वयं मेरे द्वारा भरी गई है।
- 3) मेरे द्वारा प्रस्तुत रजिस्ट्रेशन मेरा स्वयं का है एवम् पूर्णतया वैध है।
- 4) कार्य मेरे द्वारा ही सम्पादित किया जायेगा एवं इसे Sublet नहीं किया जायेगा।
- 5) किसी भी प्रकार की गलत जानकारी के लिये मैं स्वयं उत्तरदायी रहूँगा।

दिनांक :

(हस्ताक्षर संवेदक मय सील)