

# **MUNICIPAL CORPORATION KOTA**

## **(NIT NO. 11/2017-18) ('G' Schedule) (Copy No. 08)**

Name of Work : वार्ड नं. 34 स्थित गौशाला में स्नानघर बनवाने का कार्य।

Estimated Cost : **Rs. 13.35 Lacs** Earnest Money : **6675/- (0.50%)**  
**26700/- (2%)**

Tender Cost : **1500/-** Completion Period : **3 Month**

Processing Fees : **500/-**

Date of Sale of Tender : **16-05-2017 to 07-06-2017**

Date of Receipt Tender : **16-05-2017 to 07-06-2017 (Office Time)**

Date of Opening Tender : **08-06-2017 (2.00 PM) (Envelop – A)**

Date of Opening Tender : **तकनीकी बिड परीक्षण के पश्चात्।**

Issued To: \_\_\_\_\_

C.R.No. \_\_\_\_\_ Dated \_\_\_\_\_

### PART – A

S.NO	Particulars	Qty.	Rate	Amount
1	Earth Work in excavation in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 mtr. including taking out the excavated soil and depositing and refilling of jhiri with watering and ramming and disposal of surplus excavated soil as directed within a lead of 50mtr. All kinds of soil	154.36 Cum	152.00 P.cum	23462.72
2	Providing and laying in position cement concrete including curing compaction etc. complete in specified grade excluding the cost of centering and shuttering – All work upto plinth level. 1 : 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	60.16 Cum	2497.00 P.cum	150219.52
3	Providing and laying in position including curing, compaction etc. complete in specified grade excluding the cost of centering and shuttering – All work up to plinth level. 1 : 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	8.48 Cum	3711.00 P.cum	31469.28
4	Rough chisel dressed stone flooring over 20mm (AV.) thick base in CM 1 : 6 including pointing with cement mortar 1 : 2 (1 cement : 2 stone dust) with and admixture of pigment to match the shade of stone with joint thickness upto 15 mm : 45 mm thick red sand stone.	14.62 Sqm	397.00 P.sqm	5804.14
5	Random Rubble stone masonry for foundation and plinth in cement Sand mortar above 30 cm thick wall in : Cement Mortar 1 : 6 ( 1- Cement : 6 Sand )	72.30 Cum	2014.00 P.cum	145612.20

6	Providing and laying damp proof with cement concrete grade M-15 (1:2:4) mortar prepared with 15 solution of water proof compound including including two coats of hot blown bitumen (2 kg. per sqm) complete as per specification with glass strip 3 mm thick at a distance of 1 m interval. 50 mm thick	32.39 Sqm	115.00 P.sqm	3724.85
7	Plaster on new surface on walls in cement sand mortar 1 : 4 including racking of joints etc. complete fine finish. 20 mm thick	396.16 Cum	120.00 P.cum	47539.20
8	Dismantling stone rubble masonry including stacking of serviceable material and disposal of unserviceable material within 50 meters lead. In cement mortar.	7.64 Cum	392.00 P.cum	2505.92
9	Random Rubble dry stone Kharnaja under floor.	15.00 Cum	805.00 P.cum	12075.00
10	Providing and fixing steel gate grating and grills made of angles, tees, square bars or other flats black pipe with holdfast and fittings complete as per design and drawing including cutting welding and fabrication with priming coat or red oxide.	150.00 Kg.	78.00 P.Kg.	11700.00
11	Painting with enamel paint of approved brand and Manufacture to give an even shad : Two or more coats on new work.	29.60 Sqm	46.00 P.sqm	1361.60
12	Finishing wall with water proofing cement paint of approved brand and manufacture and or required shade to give an even shade including all scaffolding : Old work (one or more coats)	120.86 Sqm	33.00 P.sqm	3988.38
13	Supplying and fixing of stone linted / bed plats of approved quarry rough dressed in cement mortar 1 : 4 upto 15 cm thick.	6.04 Cum	11490.00 P.cum	69339.60
14	Providing & laying of interlocking concrete block pavement having thickness 60 mm thick as per drawing and technical specification clause 1504.	155.15 Sqm	639.63 P.sqm	99238.59
15	Providing and fabricating reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding (including cost of binding wire) all complete up to floor three level. Cold twisted deformed bars (IS:1786).	5374.11 Kg.	66.00 P.Kg.	354691.26
16	Providing and laying in position specified grade of reinforced cement concrete including curing compaction finishing with rendering in cement sand mortar 1 : 3 (1 cement : 3 coarse sand) and making good the joints excluding the cost of centering, shuttering and rein for cement all work up to plinth level 1 : 1.5 : 3 (1cement : 1.5 coarse sand : 3 graded store aggregate 20 mm nominal size	27.43 Cum	4027.00 P.cum	110460.61

17	reinforced cement concrete works in beams, suspended floors, roofs, grids having slopes upto 15°, landings balconies, shelves, chajjas,lintels, bands, plain windows sills, staircases and spiral staircases upto floor three level including curing, compaction, finishing with rendering in cement sand mortar 1 :3 (1 cement : 3 coarse sand) and making good joints excluding the cost of centering, shuttering and reinforcement : with 1 : 1.5 : 3 ( 1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size).	10.65 Cum	4280.00 P.cum	45582.00
18	Reinforcement cement concrete work in walls (any thickness) including attached pilasters, buttresses, plinth and string, courses, filters, columns, pillars, piers, abutments, post and struts etc. upto floor three level including curing, compaction, finishing with rendering in cement sand mortar 1:3 (1 cement : 3 coarse sand) and making good the joints excluding the cost of centering, shuttering and reinforcement with 1 : 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	7.56 Cum	4149.00 P.cum	31366.44
19	Providing and fixing Ist quality white / Ivory Glazed Tiles ISI marked (1S : 13753) of size 300mm x 200mm in walls, floors, steps, pillars, etc. laid on a bed of neat cement slurry finished with flush pointing in white cement mixed with pigment to match the shade of tile complete (excluding the cost of cement plaster) Category – II Bell, Thar make etc.	171.93 Sqm	563.00 P.sqm	96796.59
20	Supply & Stacking of crusher dust at site complete including loading unloading & transportation etc.	24.46 Cum	250.00 P.cum	6115.00
21	Flyash Brick masonry in foundation and plinth with Flyash bricks of class designation 75 in : Cement mortar 1:6 (1 cement : 6 coarse sand).	18.87 Cum	2696.00 P.cum	50873.52
	(a) Add extra	18.87 Cum	255.00 P.cum	4811.85
22	Centering and shuttering with plywood or steel sheets including strutting , propping, bracing both ways and removal of formwork for foundations in basements rafts, footings, strap beams, bases of columns etc. upto plinth level.	43.77 Sqm	91.00 P.sqm	3983.07
23	Centering and shuttering with plywood or steel sheets including strutting , propping, bracing both ways with wooden members and removal of form work for superstructure upto 4.5m height above plinth level for	100.80 Sqm	211.00 P.sqm	21268.80
	(a) columns, pillars, posts and struts etc.			

	(b) suspended floors, roofs landlings, staircases, balconies, griders, cantilevers, bands, coping bed plates, anchor blocks, skills, chajjas, lintels, beam etc.	7.29 Sqm	153.00 P.sqm	1115.37
	<b>TOTAL</b>			<b>1335105.51</b>

Say Rs. 13.35 Lacs

**Terms & Conditions:**

1. Conditional tender shall not be accepted.
2. In case of any error in rates or nomenclature, the same shall be paid as per B.S.R. of P.W.D. 2013.
3. निविदा दर बी.एस.आर. से कम होने पर अन्तर राशि की बैंक गारन्टी / डी. डी. विभाग में टेण्डर स्वीकृत होने के 15 दिवस के अन्दर-अन्दर जमा कराना होगा, अन्यथा धरोहर राशि जब्त की जाकर निविदा निरस्त कर दी जावेगी।

***I / We hereby agree to execute the work :***

At the rate \_\_\_\_\_ % above/below (in words)

At the rate \_\_\_\_\_ % above/below (in Figures)

***Signature of Contractor***

***Executive Engineer  
Municipal Corporation, Kota***

—प्रारूप—  
(लेटरहेड)

सहमति—पत्र

श्रीमान अधिशाषी अभियन्ता,  
नगर निगम कोटा।

**विषय :** अपनी निविदा हेतु सहमति के संबंध में।  
**प्रसंग :** निविदा क्रमांक.....

महोदय,

विषयान्तर्गत निवेदन है कि मैं सत्यनिष्ठा पूर्वक अपनी निम्न सहमति प्रस्तुत करता हूँ :-

- 1) निविदा प्रपत्र पर मेरे स्वयं के हस्ताक्षर हैं।
- 2) निविदा दर स्वयं मेरे द्वारा भरी गई है।
- 3) मेरे द्वारा प्रस्तुत रजिस्ट्रेशन मेरा स्वयं का है एवम् पूर्णतया वैध है।
- 4) कार्य मेरे द्वारा ही सम्पादित किया जायेगा एवं इसे Sublet नहीं किया जायेगा।
- 5) किसी भी प्रकार की गलत जानकारी के लिये मैं स्वयं उत्तरदायी रहूँगा।

दिनांक : .....

(हस्ताक्षर संवेदक मय सील)